

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 05/31/01

CORNER DESIGNATION: P-9

PREVIOUS RENEWALS/SURVEYS, ETC.: Corner originally established by Nicholas O. Walden, U.S. Dept. Surv., under Contract No. 209, dated July 6, 1874. Record states: Set basalt stone, 15 x 8 x 5, 8 ins. in ground, for 1/4 Sec. Cor.

Geary Kimbrell, Deputy County Surveyor, recovered this corner under Survey No. 239, dated March, 1906, but does not state what was found.

MONUMENT AND ACCESSORIES FOUND: Accepted fence corner with fences running West, East and North as best remaining evidence of the original corner location. Searched without success for stone monument at or near fence corner. Position of fence corner matches measurements by Geary Kimbrell in 1906 very well.

MONUMENT MARKING DETAIL:

T6N R33E
1/4
S20 | S21
2001
PLS 1106

MONUMENT SET:

Just South of fence corner post, set a 2 1/2" aluminum cap on a 2 1/2" x 30" aluminum pipe with top 2 inches above ground level. Cap marked as shown in "Monument Marking Detail".

From which:

A 5/8" x 30" iron rebar with a yellow plastic cap stamped "OR PLS 1106, WA PLS 17372", bears N 39 1/2° E, 70.5 feet.

A purple deep-1 magnet, buried 16" below ground level, bears S 13° E, 40.9 feet.

A blue deep-1 magnet, buried 16" below ground level, bears S 33 1/2° W, 52.2 feet.

A 5/8" x 30" iron rebar with a yellow plastic cap stamped: OR PLS 1106, WA PLS 17372", bears N 15° W, 66.3 feet.

Attached "witness" sign to wood fence post North of corner. Attached bearing object tags to 5/8" iron rebars. Buried bearing object signs with the deep-1 magnets.

LOCATION AND COMMENTS:

Corner located at fence intersection with fence's North and East-West.

OREGON STATE PLANE CO-ORDINATES, OREGON NORTH, NAD 83(91): *fti*

N: 850847.32

E: 8658515.06

FIRM: William R. Wells, PLS
P.O. Box 1696
Pendleton, OR 97801


COMPASS DECLINATION: 18° East

Witnesses: Jason Wells, LSIT
Mark Hammersla
\\6N33P9

Surveyor's Seal



William R. Wells



renews 6-30-02

RECEIVED BY

Umatilla County Surveyor

Date 9-01

Rec'd By KK

No. 01-139-C