

OREGON CORNER RESTORATION FORM

Section: 26  
Township: 6N  
Range: 34 EWM  
County: Umatilla  
Date: 12/30/99  
Corner Designation: R-17

Previous Renewals/Surveys, etc.: Original GLO corner established as a post, with pits and mounds, by Odell, under contract No. 110, in 1865.

Monument(s) & Accessories Found (Condition & Source: No evidence found, falls in road.

Monument Detail: Set 2 1/2" Aluminum Cap mon. on 5/8" rebar 13" deep in Troyer road.

Tomkins Surveying  
T6N R34E  
22 | 23  
+  
27 | 26  
1999

WA 25893 OR 2360

Monument Set (Procedures & Description):

At a computed double proportioned position using the established corners at the NW corner of S.28, the NE corner of S.26, the NW corner of S.23 and SW corner of S.26, we set the corner described above. The corners were tied and set using Trimble 4400 receivers using real time kinematic methods having standard errors of 1cm plus 2ppm times the baseline length.

New Accessories:

We set:

A 5/8" rebar w/ yellow cap stamped 'Tomkins Surveying' which bears N68°E 44.1' from the corner, and attached B.O. tag to fence post.

A 5/8" rebar w/ yellow cap stamped 'Tomkins Surveying' which bears N10°E 19.4' from the corner, and attached B.O. tag to fence post.

A 5/8" rebar w/ yellow cap stamped 'Tomkins Surveying' which bears N70°W 55.75' from the corner, and attached B.O. tag to fence post.

A 5/8" rebar w/ yellow cap stamped 'Tomkins Surveying' which bears S40°E 24.22' from the corner at the south edge of gravel.

Location & Comments:

The corner falls in Troyer Co. Rd.

Compass Declination:

19° East Dec. used to tie B.O.'s.

Firm/Agency: Tomkins Land Surveying, Inc.  
20 E. Poplar Ste. 204  
Walla Walla WA 99362

Party Chief: Thomas S. Butler

Notes: Thomas S. Butler

Witness: Brianna Slater

Surveyor's Seal

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

OREGON  
JULY 26, 1988  
PAUL W. P. TOMKINS  
2360

2/18/00

00-31-B