

OREGON CORNER RESTORATION FORM

Section: 27  
Township: 6N  
Range: 34 EWM  
County: Umatilla  
Date: 12/30/99  
Corner Designation: V-13

Previous Renewals/Surveys, etc.: Original GLO corner established as a post, with pits and mounds, by Odell, under contract No. 110, in 1865.

Monument(s) & Accessories Found (Condition & Source: No evidence found.

Monument Detail: Set 5/8" rebar with 2 1/2" Aluminum cap 14" deep in field.

TOMKINS SURVEYING  
T6N R34E  
28 | 27  
+  
33 | 34  
1999  
WA 25893 OR 2360

Monument Set (Procedures & Description):

At a computed double proportioned position using the established corners at the NW corner of S.28, the NE corner of S.26, the West 1/4 corner of S.15, and accepting a fence corner for the SW corner of S.34 (see LCR), we set the corner described above. The corners were tied and set using Trimble 4400 receivers using real time kinematic methods having standard errors of 1cm plus 2ppm times the baseline length.

New Accessories:

We set:

A 5/8" rebar w/ yellow cap stamped 'Tomkins Surveying' which bears N45°W 10.0' from the corner. Bar buried 10" deep.

A 5/8" rebar w/ yellow cap stamped 'Tomkins Surveying' which bears N45°E 10.0' from the corner. Bar buried 10" deep.

A 5/8" rebar w/ yellow cap stamped 'Tomkins Surveying' which bears S51°E 60.82' from the corner, and attached B.O. tag to fence post.

A 5/8" rebar w/ yellow cap stamped 'Tomkins Surveying' which bears S26°W 44.15' from the corner, and attached B.O. tag to fence post.

Location & Comments:

The corner falls in field 50' north of the Road, 50' West of a fence coming up from the south on the south side of the road.



Compass Declination:

19° East Dec. used to tie B.O.'s,

Surveyor's Seal

Firm/Agency: Tomkins Land Surveying, Inc.  
20 E. Poplar Ste. 204  
Walla Walla WA 99362

Party Chief: Thomas S. Butler  
Notes: Thomas S. Butler  
Witness: Brianna Slater



2/19/00

00-31-B