

# OREGON CORNER RESTORATION FORM

**Section:** 15, 16, 21, 22  
**Township:** 6 North  
**Range:** 35 East of the Willamette Meridian  
**County:** Umatilla  
**Date:** June 1, 2002

**Corner Indexing Information:** Township 6N Range 35E Corner Code N 13 (Willamette Meridian)

**Additional Identifier:** (e.g. BLM designation for the corner, street intersection, plat name, block, lot, etc.)

This corner is common to sections 15, 16, 21, and 22.

**Oregon Plane Coordinates:** N: 854213.666 E: 8727162.425

**Zone:** North **Order:** second **Datum:** NAD83-91 **Convergence:** 1°27'54.4" **Scale Factor:** .99995739

**Previous Renewals/Surveys, etc.:** Originally surveyed by U.S. Deputy Surveyor William Odell under his contract No. 110, dated 8-23-1865. The Surveyor General's notes state, "set post corner for sections 15, 16, 21, and 22, drove charred stake, dug pits, and raised mounds as per instructions." County road Survey No. 325, dated April 22, 1889, Arnold set a wedge shaped basalt stone 16"x8"x4". This stone has been found and used in subsequent surveys.

**Monument(s) & Accessories Found (Condition & Source):**

At the southwest corner of section 15, T6N R35E, found 4"x9"x17" basalt stone with a "+" on top. A 5/8" rebar along south side and two railroad spikes 4" deep along west side. Found a brick at the surface along the north side.

**Monument Set (Procedures & Description):**

**Monument Detail:**

Set 1"x30" flared end galvanized pipe with 2 1/2" brass cap at the surface stamped (see example below)	
--	--

**New Accessories: WE SET:**

A 5/8 rebar with yellow plastic cap stamped 'Tomkins Surveying' which bears North ~ 52.59 feet from the corner. Attached a Umatilla County Bearing object to the south side of locust fence post. A 5/8 rebar 12" below surface with yellow plastic cap stamped 'Tomkins Surveying' which bears N 86°E ~ 12.13 feet from the corner. No t-post or Umatilla County Bearing sign set. A 5/8 rebar 12" below surface with yellow plastic cap stamped 'Tomkins Surveying' which bears South ~ 11.97 feet from the corner. No t-post or Umatilla County Bearing sign set. A 5/8 rebar with yellow plastic cap stamped 'Tomkins Surveying' which bears S 86°W ~ 18.75 feet from the corner. Attached a Umatilla County Bearing object to a t-post.

**Location & Comments:**

**Compass Declination:**

19° East


**Firm/Agency:** Tomkins Land Surveying, Inc.  
 20 E. Poplar, Suite 204  
 Walla Walla, WA 99362

**Party Chief:** Bryan Martin  
**Notes:** Bryan Martin  
**Witness:** Eric Flowers

**Surveyor's Seal**



*Paul W. Tomkins*



*renews 6/30/04*  
*6/30/02*