

OREGON CORNER RESTORATION FORM

Section 30 Township 6N Range 35E  
County Umatilla Date 4/10/03

CORNER DESIGNATION

V-3


- Condition Report Only
- Not Found
- Renewed
- Unrecorded
- Surveyed In
- Referenced Out

Previous Renewals/Surveys, etc.:

Odell and Lewis, under Contract No. 110, dated February 7th, 1865, drove charred stake, dug pits, and raised mound.

Monument(s) & Accessories Found: (Condition and Source)  
None

Monument Detail



Monument Set (Procedures and Description):

Set a 5/8" X 30" iron rebar with yellow plastic cap marked "UCPWD...LS2627" approximately 4" below the surface of Tucholke Road by single proportion between the monuments found at the southwest and southeast corners of the section based on Odell and Lewis' survey.

New Accessories:

- A 5/8" iron rebar with yellow plastic cap marked "LS2627" bears N53°31'04"W, 22.93' (a wood fence post with bearing object tag bears 0.6' north from pin).
- A 5/8" iron rebar with yellow plastic cap marked "LS2627" bears N22°43'27"E, 15.50' (a wood fence post with bearing object tag bears 0.4' north from pin).
- A 5/8" iron rebar with yellow plastic cap marked "LS2627" bears S65°03'29"E, 49.41' (a wood fence post with bearing object tag bears 0.4' south from pin).
- A 5/8" iron rebar with yellow plastic cap marked "LS2627" bears S16°24'02"W, 27.18' (a wood fence post with bearing object tag bears 0.6' south from pin).

Location and Comments: Compass Declination: N/A Surveyor's Seal

From the 4-way intersection of Highway 332, Ringer Road, and Umepine Road in Umepine, travel south on Ringer Road for 1 mile to a sharp curve left, at which point Ringer Road becomes Tucholke Road. Travel east on Tucholke Road approximately 1/2 mile to the corner, which is a 5/8" rebar with yellow plastic cap buried 4" below the road surface at the intersection of fence lines north and south.

Firm/Agency:  
Umatilla County  
Road Department

Address:  
3920 Westgate  
Pendleton, Oregon 97801

Party Chief:  
Gary Roberts  
Notes:  
Gary Roberts  
Witness:  
None

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Doug K. Nelson*  
OREGON  
JULY 20, 1993  
GARY R. ROBERTS  
2627

RENEWS 12/31/2004

Oregon State Plane Coordinates  
NAD '83 ('91) North Zone 3601 (International Feet)

Northing: 843,256.18  
Easting: 8,714,153.75

RECEIVED BY

Umatilla County Surveyor

Date 4-03

Rec'd By KK

No. 03-57-B