


C L I F I E D R E C O R D O F L A N D C O R N E R M O N U M E N T A T I O N

HISTORY OF ORIGINAL CORNER ESTABLISHMENT:

This area was originally surveyed by Odell & Lewis under General Land Office contract no. 110, dated Feb. 7, 1865. At this corner he "Set post and stone mound with charred stake as per instructions" for 1/4 corner common to Sec. 2, T5N, R35E & Sec. 35, T6N, R35E.



DESCRIPTION OF CORNER EVIDENCE FOUND:

Found 2 1/2" dia. Brass Cap (Umitilla County) set in concrete, inside of a Monument case at the centerline of State highway 339 (City of M-F, Lamb St.) Stamped "COUNTY SURVEY OR., PLS 933, 1980.

R35E

DESCRIPTION OF MONUMENT AND ACCESSORIES I ESTABLISHED TO PERPETUATE THE ORIGINAL LOCATION OF THIS CORNER:

At the position of the found 2 1/2" B.C., I set a 2" dia. X 24" long pipe in concrete inside of a monument case. In the top of the pipe I set a 2 1/2" dia. Brass Cap in concrete marked as shown, from which:


A Mag nail with a 1 1/2" dia. washer, marked APA, PLS 2537, 2003, set in top of the new curb bears N50°W, 24.1 feet.

A Mag nail with a 1 1/2" dia. washer, marked APA, PLS 2537, 2003, set in top of the new curb, bears N35°E, 32.8 feet.

A Mag nail with a 1 1/2" dia. washer, marked APA, PLS 2537, 2003, set in top of the new curb, bears S41°E, 29.2 feet.

A Mag nail with a 1 1/2" dia. washer, marked APA, PLS 2537, 2003, set in top of the new curb, bears S45°W, 25.4 feet.

Note: All RP's drilled and set in concrete curb.



I hereby certify that the above corner position was perpetuated as hereon described in August of 2003.

renew 12/31/04

Harmon E. McLendon, PLS 2537

Witnesses: Thomas Page, survey assistant, William D. Vixie, EIT

RECEIVED BY
Umatilla County Surveyor
Date 2-04
Rec'd By KK
No. 04-46-R