

**OREGON CORNER RESTORATION FORM**

COUNTY: Umatilla. DATE: 07/29/08

CORNER DESIGNATION: L-9, The East One-Quarter corner of Section 17, Township 6 North, Range 36 East, W.M..

PREVIOUS RENEWALS/SURVEYS ETC: Corner originally set by Odell & Lewis under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Corner falls in a field with no features.

**MONUMENT MARKING DETAIL:**

T6N R36E  
1/4  
S17 | S16  
2008  
PLS 1106

MONUMENT SET: Reestablished Corner position by single proportionate measure between the reestablished Southeast Corner and Northeast Closing Corner of Section 17. At the reestablished corner point, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe, with cap buried 23" below ground level, marked as shown in "Monument Marking Detail".

New accessories:

- A silver deep-1 magnet bears North 75° East, 24.4 feet.
  - A purple deep-1 magnet bears South 20° East, 31.7 feet.
  - A blue deep-1 magnet bears South 53° West, 33.5 feet.
  - An orange deep-1 magnet bears North 20° West, 35.1 feet.
- All deep-1 magnets are buried 20" below ground level with bearing object signs.

LOCATION AND COMMENTS: Corner falls in fallow field with no features.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 857479.45  
E = 8753548.32

FIRM: Wells Surveying  
P.O. Box 1696  
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

\6N36L9

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William R. Wells*

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

*Renews 6-30-10*