

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 03/12/08

CORNER DESIGNATION: V-23, The North One-Quarter Corner of Section 36, Township 6 North, Range 36 East, W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Odell & Lewis under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post. Drove charred stake; dug pits & raised mound, as per instructions.

John Kimbrell claims to have recovered this corner during his survey recorded at Book 1, Page 492, Record of Private Surveys. Kimbrell does not state what was found, and his measured distance from the Northeast corner of Section 36, (42.43 chains), does not agree well with present measurements or the original GLO record..

MONUMENT AND ACCESSORIES FOUND: None.

MONUMENT MARKING DETAIL:

T6N R36E
1 S25
4 S36
2008
PLS 1106

MONUMENT SET: Corner point was reestablished at the intersection of a rounded field line with field berms extending North and West. There is also a field line extending East, beginning about 1/4 mile East of corner point. At the reestablished corner point, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with the cap buried 18" below ground level, marked as shown in the "Monument Marking Detail".

New accessories:

- A silver deep-1 magnet bears North 51 1/2° East, 32.5 feet.
- A purple deep-1 magnet bears South 25° East, 39.4 feet.
- A blue deep-1 magnet bears South 35 1/2° West, 38.0 feet.
- An orange deep-1 magnet bears North 57 1/2° West, 32.1 feet.
- Deep-1 magnets are buried 24" below ground level with bearing object signs.

LOCATION AND COMMENTS: Falls at a rounded field corner with field berms North and West and another field line extending East, starting 1/4 mile East of corner.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 844898.15
E = 8772550.98

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

\6N36V23

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Expires 6-30-10

09-10-C