

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla. DATE: 03/05/08

CORNER DESIGNATION: V-7, The North One-Quarter Corner Section 32, Township 6 North, Range 36 East, W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Odell & Lewis, under GLO Contract No. 110, dated February 7, 1865. Notes state: Set 1/4 Sec. post; dug pits; drove charred stake & raised mound, as per instructions.

MONUMENT AND ACCESSORIES FOUND: None. Falls in irrigated wheat field, South of line of irrigation risers running East-West.

MONUMENT MARKING DETAIL:

T6N R36E

1 S29

4 S32

2008

PLS 1106

MONUMENT SET: Corner point was reestablished by single proportion measure between accepted Northwest Corner of Section 32 and the accepted Northeast Corner of Section 32. At reestablished corner point, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with cap buried 18" below ground level, marked as shown in "Monument Marking Detail".

New accessories:

A 4" irrigation riser with a 4" aluminum cover pipe bears North 84° East, 67.9 feet.

A purple deep-1 magnet bears South 41 1/2° East, 34.2 feet.

A blue deep-1 magnet bears South 40 1/2° West, 40.5 feet.

A 4" irrigation riser with a 4" aluminum cover pipe bears North 72° West, 55.6 feet.

The deep-1 magnets are buried 22" below ground level with bearing object signs.

No bearing object signs were attached to the risers.

LOCATION AND COMMENTS: Falls in irrigated wheat field South of riser line, no nearby occupation features.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 844237.48

E = 8751334.88

FIRM: Wells Surveying

P.O. Box 1696


Pendleton, OR 97801

COMPASS DECLINATION: 18° East


Surveyor's Seal

Witnesses: Jason Wells, LSIT

\6N36V7



William R. Wells



Renews 6-30-10

09-10-C