

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 04/12/08

CORNER DESIGNATION: J-25, The Northeast Corner of Section 13, Township 6 North, Range 36 East, W.M..

PREVIOUS RENEWALS/SURVEYS ETC.: Corner originally established by Odell & Lewis under GLO Contract No. 110, dated February 7, 1865. Notes state: Set post for Cor. to fractional Secs. 13 & 18. Drove charred stake; dug pits & raised mound, as per instructions.

Dwight Bartleson established a monument for this corner under Survey No. 99-282-B.

MONUMENT AND ACCESSORIES FOUND: Found 2 3/8" brass cap on galvanized iron pipe as established under Survey No. 99-282-B. This monument was not held.

MONUMENT MARKING DETAIL:

T6N
S13 WA
S13 | S18 OR
R36E | R37E
C | C
2008
PLS 1106

MONUMENT SET: I reestablished this corner on the parallel of latitude on the State Line, holding the Northerly projection of a old fence line, (posts but no wire), found Southerly of the South line of the wheat field, for departure. At reestablished corner point, set a 2 3/8" brass cap on a 1 1/4" x 30" galvanized iron pipe with cap buried 18" below ground level, marked as shown in "Monument Marking Detail".

New accessories:

The brass cap monument from Survey No. 99-282-B, buried 12" below ground in a wheat field, bears North 85° 45'36" West, 89.75 feet.

A silver deep-1 magnet bears North 52 1/2° East, 28.3 feet.

A purple deep-1 magnet bears South 42° East, 32.6 feet.

An orange deep-1 magnet bears North 34 1/2° West, 26.1 feet.

All deep-1 magnets are buried 20 inches below ground level, and a bearing object sign is buried with them.

LOCATION AND COMMENTS: Falls in wheat field. There are no nearby features. There is a old fence line, extending North-South, South of the wheat field.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 858917.93

E = 8774852.13

FIRM: Wells Surveying
P.O. Box 1696
Pendleton, OR 97801

COMPASS DECLINATION: 18° East

Surveyor's Seal

Witnesses: Jason Wells, LSIT

16N36J25

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Expires 6-30-10

09-10-C