

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla **DATE:** 01/15/2015

CORNER DESIGNATION: K-9, Closing Corner for Sections 16 and 17, Township 6 North, Range 37E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by A.H. Simmons for Deputy Surveyor George Williams under his contract No. 176 dated October 23, 1872; his notes state "Set stone 12" x 14" x 18" for cor. to fractional section 16 and 17.

MOUNUMENT AND ACCESSORIES FOUND:

Found stone 12" x 14" x 18" bears S. 83° W, 32.50 ft. from existing fence corner. Held position for closing corner.

MOUNUMENT MARKING DETAIL:

LS 02820
T 6N R 37E
S 17 CC
S 17 | S 16
T 6N R 37E
1/2015

MOUNUMENT AND ACCESSORIES SET:

At the surveyed position of the found stone, set a 2½" brass cap on a 1½" x 30" galvanized iron pipe, 2" above ground with found 12" x 14" x 18" stone in hole directly west of said monument from which:

A 16" diam. fir bearing N. 83° W. 41.00 ft.

A silver "DEEP-1" magnet and bearing sign buried 20" bears N. 32° E., 15.50 ft.

A 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S. 34° E., 25.00 ft.

A 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S. 33° W., 15.00 ft.

LOCATION AND COMMENTS:

Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 859202.50

E = 8785394.80

COMPASS DECLINATION: 15° East


SURVEYORS' SEAL:

FIRM: HDJ Design Group
5 N. Colville, Suite 200
Walla Walla WA 99362

WITNESSES: Joseph R. Latimer
Corey A. West



Greg E. Flowers



RENEWS 12/31/15

6/29/2015