

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 01/13/2015

CORNER DESIGNATION: L-5, Quarter Corner Section for Sections 17 and 18, Township 6 North, Range 37E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by A.H. Simmons for Deputy Surveyor George Williams under his contract No. 176 dated October 23, 1872; his notes state "Set stone 6" x 8" x 10" for ¼ Sec. Cor.

MOUNUMENT AND ACCESSORIES FOUND:

No evidence found.

MOUNUMENT MARKING DETAIL:

LS 02820
T 6N
S 18 | S 17
R 37E
1/2015

MOUNUMENT AND ACCESSORIES SET:

At the surveyed position set a 2½" brass cap on a 1½" x 30" galvanized iron pipe, 22" below ground, in farmed field, from which:

Deposited an Orange "DEEP 1" magnet, 18" deep, with bearing tag, bears N. 44° W., 20.00 feet distance.

Deposited a silver "DEEP 1" magnet, 18" deep, with bearing tag, bears N. 48° E., 14.50 feet distance.

Deposited a pink "DEEP 1" magnet, 18" deep, with bearing tag, bears S. 44° E., 10.00 feet distance.

Deposited a blue "DEEP 1" magnet, 18" deep, with bearing tag, bears S. 42° W., 10.00 feet distance.

LOCATION AND COMMENTS:

Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 858254.97

E = 8780111.91

COMPASS DECLINATION: 15° East

SURVEYORS' SEAL:

FIRM: HDJ Design Group
5 N. Colville, Suite 200
Walla Walla WA 99362

WITNESSES: Joseph R. Latimer
Corey A. West



Greg E. Flowers
OREGON
JUNE 30, 1997
GREG E. FLOWERS
02820LS

RENEWS 12/31/15

06/29/2015

15-063-C