

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla **DATE:** 1/30/2015

CORNER DESIGNATION: N-13, Corner of Sections 15, 16, 21 and 22, Township 6 North, Range 37E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by A. H. Simmons for US Deputy Surveyor George Williams under his contract No. 176 dated July 20, 1872. His notes state "Set stone 10 x 15 x 30, pits for the Cor. to Secs. 15, 16, 21 and 22."

MOUNUMENT AND ACCESSORIES FOUND:

No evidence found.

MOUNUMENT MARKING DETAIL:

LS 02820
T 6N R
S 16 | S 15 37
S 21 | S 22 E
1/2015

MOUNUMENT AND ACCESSORIES SET:

At the surveyed position, set a 2½ ins. brass cap on a 1½ in. galvanized iron pipe, 5 ins. above ground surface, surrounded with a mound of stone, from which:

- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N. 58° W., 4.00 ft.
- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N. 55° W., 5.20 ft.
- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S. 40° E., 6.00 ft.
- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S. 25° W., 7.00 ft.
- Set a "T" post 2 feet NE of monument.

LOCATION AND COMMENTS:

Location is on a steep southwest facing slope. Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 855932.25
E = 8790602.84

COMPASS DECLINATION: 15° East


SURVEYORS' SEAL:

FIRM: HDJ Design Group
5 N. Colville, Suite 200
Walla Walla WA 99362

WITNESSES: Thomas J. Boshart
Felipe G. Hernandez



Greg E. Flowers



RENEWS 12/31/15

06/24/2015