

**OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:**

N = 856400.11

E = 8798366.59

**COMPASS DECLINATION:** 15° East

**SURVEYORS' SEAL:**

**FIRM:** HDJ Design Group  
5 N. Colville, Suite 200  
Walla Walla WA 99362

**WITNESSES:** Thomas J. Boshart  
Felipe G. Hernandez

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Greg E. Flowers*

OREGON  
JUNE 30, 1997  
GREG E. FLOWERS  
02820LS

RENEWS 12/31/15

*06/29/2015*

# OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 06/09/2014

CORNER DESIGNATION: N-19, Quarter Corner for Sections 14 and 23, Township 6 North, Range 37E, W.M.

## PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by A. H. Simmons for US Deputy Surveyor George Williams under his contract No. 176 dated July 20, 1872. His notes state "Set post for 1/4 Sec. Cor. from which:  
A Tamarac 20 ins. diam., bears N50° E., 19 lks. dist.,  
A Fir 8 ins. diam., bears S15° E., 39 lks. dist."

BLM Cadastral Surveyor C. Albert White in his April 21, 1965 for Group 572 stated in his notes:  
"Point for the 1/4 sec. cor. of secs. 14 and 23, at proportionate distance; there is no remaining evidence of the original corner.

Set an iron post 28 ins. long 2 1/2 ins. diam., 24 ins. in the ground with a brass cap marked:

1/4  $\frac{S\ 14}{S\ 23}$   
T6N R37E  
1965

from which

A Fir 10 ins. diam., bears N14° E., 42 lks. dist., mkd. 1/4 S14 BT.

A Fir 7 ins. diam., bears S18° E., 63 lks. dist., mkd. 1/4 S23 BT.

## MOUNUMENT AND ACCESSORIES FOUND:

Found a 3 1/2 BLM brass cap on a 2 1/2 inch iron pipe marked 1/4 S14 and S23 1965, +/- .2 ins. above ground as described in BLM Survey.

A 26 ins. diam., fir with healed blaze and tag bears N 14° E., 27.70 ft. dist.

A 24 ins. diam., fir with healed blaze and tag bears S 18° E., 41.60 ft. dist.

## MOUNUMENT MARKING DETAIL:



## MOUNUMENT AND ACCESSORIES SET:

A 12 ins. diam., White Fir bears, N 53° E., 10.90 ft. mk. T6NR37E 1/4 S14 BT, blazed, scribed, tagged and painted,

An 18 ins. diam., White Fir bears, S 69° W., 33.60 ft. mkd. T6NR37E 1/4 S23 BT, blazed, scribed, tagged and painted,

Painted the 26 ins. diam., fir bearing tree

Painted the 24 ins. diam., fir bearing tree

## LOCATION AND COMMENTS:

Bearings taken with Silva hand compass and distances measured with a steel tape.