

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla **DATE:** 0/13/2015

CORNER DESIGNATION: N-3, Quarter Corner for Sections 18 and 19, Township 6 North, Range 37E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by A. H. Simmons for US Deputy Surveyor George Williams under his contract No. 176 dated July 20, 1872. His notes state "Set stone 6 x 8 x 10 mound and pits for 1/4 Sec. Cor.

MOUNUMENT AND ACCESSORIES FOUND:

No evidence found.

MOUNUMENT MARKING DETAIL:

LS 02820
T 6N
1/4 $\frac{S 18}{S 19}$
R 37E
1/2015

MOUNUMENT AND ACCESSORIES SET:

At the surveyed position, set a 2½ ins., brass cap on a 1½ in. galvanized iron pipe. 20" deep in plowed field, with flagging from which:
Deposited an orange "Deep-1" magnet, 18 ins. deep, with bearing tag, bears N. 46° W., 15.00 ft.
Deposited a silver "Deep-1" magnet, 18 ins. deep, with bearing tag, bears N. 44° E., 10.00 ft.
Deposited a pink "Deep-1" magnet, 18 ins. deep, with bearing tag, bears S. 46° E., 10.00 ft.
Deposited a blue "Deep-1" magnet, 18 ins. deep, with bearing tag, bears S. 46° W., 20.00 ft.

LOCATION AND COMMENTS:

The corner falls in a farmed field. Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 855563.03
E = 8777560.58

COMPASS DECLINATION: 15° East


SURVEYORS' SEAL:

FIRM: HDJ Design Group
5 N. Colville, Suite 200
Walla Walla WA 99362

WITNESSES: Joseph R. Latimer
Cory A. West



Greg E. Flowers



RENEWS 12/31/15

06/29/2015

15-063-C