

# OREGON CORNER RESTORATION FORM

COUNTY: Umatilla    DATE: 01/30/2015

CORNER DESIGNATION: P-13, Quarter Corner Section for Sections 21 and 22, Township 6 North, Range 37E, W.M.

**PREVIOUS RENEWALS/SURVEYS ETC:**

Originally surveyed by A.H. Simmons for Deputy Surveyor George Williams under his contract No. 176 dated October 23, 1872; his notes state "Set post and stone 4 x 8 x 12 mound, stones and pits for 1/4 Sec. Cor.

**MOUNUMENT AND ACCESSORIES FOUND:**

No evidence found.

**MOUNUMENT MARKING DETAIL:**

LS 02820  
T 6N | R 37E  
S 21 | S 22  
    |  
    1/4  
    1/2015

**MOUNUMENT AND ACCESSORIES SET:**

At the surveyed position, set 2 1/2" brass cap on a 1 1/2" x 30" galvanized iron pipe 3" above ground surface with the following accessories:

- A 5/8" x 30" iron rebar with yellow plastic cap "TLS-HDJ" bears N72°W, 8.00 feet distance.
- A 5/8" x 30" iron rebar with yellow plastic cap "TLS-HDJ" bears N63°E, 10.00 feet distance.
- A 5/8" x 30" iron rebar with yellow plastic cap "TLS-HDJ" bears S50°E, 11.50 feet distance.
- A 5/8" x 30" iron rebar with yellow plastic cap "TLS-HDJ" bears S45°W, 15.00 feet distance.

**LOCATION AND COMMENTS:**

Quarter corner is on a south facing slope. Bearings taken with Silva hand compass and distances measured with a steel tape.

**OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:**

N = 853351.45  
E = 8790604.92

COMPASS DECLINATION: 15° East

SURVEYORS' SEAL:

FIRM: HDJ Design Group  
5 N. Colville, Suite 200  
Walla Walla WA 99362

WITNESSES: Joseph R Latimer  
Cory A. West



RENEWS 12/31/15

06/29/2015