

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla **DATE:** 12/30/2014

CORNER DESIGNATION: R-13, Section Corner common to Sections 21, 22, 27 and 28 Township 6 North, Range 37 East, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by George Williams, Contract No. 176, dated July 20, 1872. His notes state "Set post and marked stone, mound and pits for the cor. of Secs 21, 22, 27 and 28.

MOUNUMENT AND ACCESSORIES FOUND:

No evidence found.

MOUNUMENT MARKING DETAIL:

LS 02820
T6N R37E
S21 | S22
S28 | S27
12/2014

MOUNUMENT AND ACCESSORIES SET:

At the surveyed position, set a 2½" brass cap on 1½" x 30" galvanized iron pipe projecting 0.65" above ground, from which:

- A 5/8" x 30" iron rebar with yellow plastic cap "TLS-HDJ" bears N51°E, 5.00 feet distance.
- A 5/8" x 30" iron rebar with yellow plastic cap "TLS-HDJ" bears N50°E, 10.00 feet distance.
- A 5/8" x 30" iron rebar with yellow plastic cap "TLS-HDJ" bears S49°E, 17.40 feet distance.
- A 5/8" x 30" iron rebar with yellow plastic cap "TLS-HDJ" bears S55°W, 3.60 feet distance.

LOCATION AND COMMENTS:

Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 850770.64
E = 8790606.99

COMPASS DECLINATION: 15° East

SURVEYORS' SEAL:

FIRM: HDJ Design Group
5 N. Colville, Suite 200
Walla Walla WA 99362

WITNESSES: Joseph R. Latimer
Cory A. West



OREGON
JUNE 30, 1997
GREG E. FLOWERS
02820LS
RENEWS 12/31/15

06/29/2015