

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla **DATE:** 12/18/2014

CORNER DESIGNATION: V-15, Quarter Corner for Sections 27 and 34, Township 6 North, Range 37E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by A.H. Simmons for Deputy Surveyor George Williams under his contract No. 176 dated October 23, 1872; his notes state "Set post for quarter corner for Sections 27 & 34 mound of rock on hillside facing south.

MOUNUMENT AND ACCESSORIES FOUND:

No evidence found.

MOUNUMENT MARKING DETAIL:

T6N R37E
 $\frac{S27}{S34}$ 1/4
12/2014
LS 02820

MOUNUMENT AND ACCESSORIES SET:

At the surveyed position, set a 2½" brass cap on 1½" galvanized iron pipe, 3" above ground marked ¼ corner of Sections 27 and 34, T6N,R37E by LS 02820 on 12/ 2014, from which;
Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N46°W, 15.00 feet.
Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N43°E, 15.00 feet.
Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S43°W, 15.00 feet.
Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S42°E, 28.00 feet.

LOCATION AND COMMENTS:

Located on a steep southwest slope with no trees. Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 845778.40
E = 8793402.94

COMPASS DECLINATION: 15° East


SURVEYORS' SEAL:

FIRM: HDJ Design Group
 5 N. Colville, Suite 200
 Walla Walla WA 99362

WITNESSES: Joseph R. Latimer
 Corey A. West



Greg E. Flowers



RENEWS 12/31/15

06/29/2015

15-063-C