

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 10/01/2014

CORNER DESIGNATION: V-7, Quarter Corner for Sections 29 and 32, Township 6 North, Range 37E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by A.H. Simmons for Deputy Surveyor George Williams under his contract No. 176 dated October 23, 1872; his notes state "Set post and mark stone mound and pits for quarter section corner to Sections 29 & 32.

MOUNUMENT AND ACCESSORIES FOUND:

No evidence found.

MOUNUMENT MARKING DETAIL:

T6N R37E
 S29 1/4
 S32
12/2014
LS 02820

MOUNUMENT AND ACCESSORIES SET:

At the surveyed position, set a 2 1/2 inch Brass Cap on 1 1/2" galvanized iron pipe, two inches above ground marked 1/4 corner of Sections 29 and 32, T6N,R37E by LS 02820 on 12/ 2014, from which:

- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N42°W, 20.00 feet.
- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears N52°E, 10.00 feet.
- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S47°W, 10.00 feet.
- Set a 5/8" iron rebar with yellow plastic cap marked "TLS-HDJ" bears S43°E, 12.00 feet.

LOCATION AND COMMENTS:

Track road approximately 300 feet NE, no trees and good dirt. Bearings taken with Silva hand compass and distances measured with a steel tape.

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 845313.04
E = 8783022.66

COMPASS DECLINATION: 15° East


SURVEYORS' SEAL:

FIRM: HDJ Design Group
 5 N. Colville, Suite 200
 Walla Walla WA 99362

WITNESSES: Joseph R. Latimer
 Corey A. West



Greg E. Flowers



RENEWS 12/31/15

06/29/2015

15-063-C