

OREGON STATE PLANE COORDINATE, North Zone, NAD 83(91), International Feet:

N = 843619.689

E = 8806540.56

COMPASS DECLINATION: 15° East

SURVEYORS' SEAL:

FIRM: HDJ Design Group
5 N. Colville
Walla Walla WA 99362

WITNESSES: Joseph R. Latimer
Felipe G. Hernandez
Mark F. Wendover

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JUNE 30, 1997
GREG E. FLOWERS
02820LS

RENEWS 12/31/15

06/29/2015

OREGON CORNER RESTORATION FORM

COUNTY: Umatilla DATE: 06/10/2014

CORNER DESIGNATION: X-25

Quarter Corner common to Section 36 T6N R37E and Section 31 T6N R38E, W.M.

PREVIOUS RENEWALS/SURVEYS ETC:

Originally surveyed by William H. Odell and William S. Lewis in 1865, their notes state "made corner for ¼ Section on Yew tree 2 inches diameter from which a fir 20 inch diameter bears S47°E 12 links, a yew 8 inch diameter bears S38°W, 25 links.

Surveyor Wayne O. Harris noted in his June 27, 1961 survey, shown on Umatilla County Survey, record of surveys 03-291-A (Drawing Number 61-112-C), "Found witness tree – set 2" Iron pipe."

In 1991 BLM Cadastral Surveyor Richard L. Johnson found the original corner tree, a 6 inch yew with no marks, from which the remains of the original bearing trees:

A fir snag, 40 inch diameter bears S60°E 12 links distance.

A root hole, bears S38°W 25 links distance.

A reference monument by Wayne Harris, is a 2 inch iron pipe protruding 12" above ground bears S. 60½° E., 1 link distance.

Johnson set two new references;

A Yew 11 inch diameter bears S. 8½° W., 37½ links marked ¼ S36 BT.

A 2½ inch stainless steel post for a reference monument bears N. 45° E., 10 links with a brass cap marked RM¼ S 31 T6NR38E 6.6 to COR 1991 and an arrow pointing to the corner.

MOUNUMENT AND ACCESSORIES FOUND:

Found the corner tree, a 6 inch diameter Yew.

A 2 inch iron pipe bears S. 60¼° E., 0.66 feet

The remains of the original bearing tree a 40 inch diameter fir snag bears S. 60° W., 7.9 feet

A 12 inch diameter Yew marked ¼S36 BT bears S. 8½° W., 24.7 feet.

A 2½ inch stainless steel pipe with a BLM 3 ½" inch brass cap reference monument bears N45°E 6.6 feet marked RM¼S31 T6N38E 6.6 feet to cor. 1991 with an arrow pointing to the corner.

MOUNUMENT MARKING DETAIL:

RM
¼ S31
6.6 FT.
TO COR
T6N R38E
1991

MOUNUMENT AND ACCESSORIES SET:

An 8 inch diameter Douglass Fir bears N. 24° W., 9.1 feet marked ¼T6NR37E S36 BT.

A 9 inch diameter Spruce bears N. 86° W., 10.1 feet marked ¼ T6NR38E S31BT.

LOCATION AND COMMENTS:

Corner is in a grove of trees near the intersection of two dirt roads, a huge post of a gate across a dirt road bears S. 52½° W., 40.5 feet, the cent of the 2nd dirt road running NW and SE bears N. 45° E., 25 Feet. Bearings taken with Silva hand compass and distances measured with a steel tape.