

USDA-FOREST SERVICE

Index

File No. L-23

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. \_\_\_\_\_

Cor. No. 1/4 Cor

T 6S R. 29E

R.D. Ukiah


County Morrow

Merid. Willamette

N.F. Umatilla

State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None

PHOTO IDENTIFICATION DATA

Photo No. \_\_\_\_\_

Filed At. \_\_\_\_\_

Object Ident. \_\_\_\_\_

Ident. By \_\_\_\_\_

*Signature*

PLANE COORDINATE POSITION DATA

State \_\_\_\_\_ Zone \_\_\_\_\_

X \_\_\_\_\_

Y \_\_\_\_\_

Estab. By \_\_\_\_\_

*Signature*

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

Corner is approximately 500' East of road running North and South through section. Location tag on East side of road.

Title

PLS  
Division

346  
Headquarters

9/79  
Date

7100-52-(3/68)

**CORNER RECORD (PERPETUATION)**

**MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT**

Set 32" X 2" flanged iron pipe with brass cap marked

T6S R29E  
0 $\frac{1}{4}$  S13  
1979  
PLS 346

**ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE**

Ponderosa Pine, 8" Dia., BRS. N55 3/4<sup>o</sup>E., 42.3 Ft. Distance.  
Ponderosa Pine, 8" Dia., BRS. N62 1/2<sup>o</sup>W., 35.2 Ft. Distance.  
6' Iron Fence Post with "Survey Monument" sign within 5' of Corner.

Work Done By Wayne O. Harris Title PLS Date 9/79 State Registration No. or Agency 346  
Certified Cor. Record Prepared? YES XXX Filed At: Morrow Co. Surveyor Office Date           

**REMARKS**