


0-01

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishments:

Corner not established in the original survey of 1881 by Meldrum and Campbell.




No record of subsequent remonumentation was found in county records.

Description of corner evidence found:

( See map of Survey, dated December, 1975 )

Description of monument and accessories established to perpetuate the original location of this corner

At corner position I set 2 1/2" X 30" iron pipe with brass cap marked as shown 22" in ground, from which:  
 A 24" Pine bears N 83° E, 61.0 ft. marked N 1/16 S19 BT.  
 A 12" Pine bears N 75° W, 28.0 ft. marked N 1/16 S24 BT.  
 Raised mound of stone.  
 Set steel fence posts 5+ ft. East and South.



REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Dwane L. Griffith*

OREGON  
JULY 10, 1904  
DJANE L. GRIFFITH  
644

Brass Washer nailed to BT blazes.  
 Used steel tape and magnetic compass with 19° 30' East declination.  
 Measured to center of all BTs.

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of.....

..... by ..... (COUNTY OFFICIAL) (DEPUTY)

0-1

S-58-M