


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

M 1.

History of original corner establishment:
Unsurveyed - subdivided section



No record of subsequent remonumentation found in County Record.


Description of corner evidence found:
None.

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 2½" x 30" iron pipe 26" in ground with brass cap marked as shown:
From which I scribed Bearing Trees.

A 11" fir bears S. 85° 34' E 33.6 ft. mkd. ¼ S.3 BT.
A 11" fir bears S. 29° 34' W. 18.3 ft. mkd. ¼ S.3 BT.

Nailed a brass washer mkd. PLS 933 to the BT blaze of both trees. Set steel fence post 4 ft. East of corner. Corner is 3 ft. South of E-W fence line. Used compass with 20° East variation and steel tape, measuring to the center of BTs.



Office of.....County Surveyor..... County of.....Umatilla.....
 State of.....Oregon..... I hereby certify that the within instrument was filed in this office
 for record on the.....17 day of.....July....., 19.....
David H. Krumbein by.....
 (COUNTY OFFICIAL) (DEPUTY)

A-15

M-64