


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1881
by Frank W. Campbell under Contract No. 380.

Surveyor General Record States:

79.72 intersect: 1st Parallel 8.00 chs. East of corner to
secs. 33 and 34. Set a pine post for dosing cor. from which:

- A pine 12 in. in diam. brs. S. 49° E. 165 lks. dist.
- A pine 20 in. in diam. brs. S. 56° W. 45 lks. dist.
- A pine 20 in. in diam. brs. North 20 lks. dist.



No record of subsequent remonumentation found in County Records.

Description of corner evidence found:

I did not find the original corner post. I establish this corner from 2 live
original bearing trees. From the corner point:

- A 20" pine bears S. 49° E. 108.9 feet with scribing visible in opened blaze.
- A 21" pine bears S. 50° W. 29.7 feet marked S. 3 CC BT.
- A stump hole bears North 13.2 ft. no remains of BT.

Description of monument and accessories I established to perpetuate the
original location of this corner:

At the corner point: Set a 2½"x30" galvanized iron pipe 22" in the ground with brass
cap marked as shown.


As both original BTs are healthy I do not scribe new BTs. Set steel fence post 5 ft.
East of corner. Raised a mound of stone, 3 ft. base to top of pipe. Corner is 50
ft. South of E-W fenceline. Used compass with 20° E. Variation and steel tape,
measuring to face of blaze of old BTs.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert D. Bagett

OREGON
JULY 12, 1963
ROBERT D. BAGETT
598

Sept. 30, 1976



Office of..... County Surveyor..... County of..... Umatilla.....
State of..... Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

A-17

S-60-m

4-1-11