


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:  
Unsurveyed - subdivided section



No record of subsequent remonumentation found in County Record.

Description of corner evidence found:

None.

Description of monument and accessories | established to perpetuate the original location of this corner:

Set 2 1/2" x 30" iron 14" in ground with brass cap marked as shown.  
From which I scribed Bearing Trees:

- A 11" pine bears N. 85°43' E. 21.3 ft. mkd. N.W. 1/16 S.2 BT.
- A 13" fir bears N. 65°57' W. 41.6 ft. mkd. N.W. 1/16 S.2 BT.

Nailed a brass washer mkd. PLS 933 to the BT blaze on both trees.  
Set steel fence post 3 ft. North of corner. Raised mound of stone 3 ft. base within 5" of top of pipe. Used transit and steel tape, measuring to the center of BTs.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*David H. Krumbein*

OREGON  
JULY 17, 1970  
DAVID H. KRUMBEIN  
933



Office of.....County Surveyor..... County of.....**Umatilla**.....  
 State of.....**Oregon**....., I hereby certify that the within instrument was filed in this office  
 for record on the..... day of....., 19.....  
*David H. Krumbein*..... by.....  
 (COUNTY OFFICIAL) (DEPUTY)

B-18