

USDA-FOREST SERVICE

Index File No. C-13

CORNER RECORD (SEARCH)


(Ref. FSM 7151.4)

Traet or Survey No. _____ Cor. No. _____

T 6S. R. 30E. R.D. Ukiah County Umatilla

Merid. Willamette N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None

Set brass cap

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

None

PHOTO IDENTIFICATION DATA

Photo No. _____

Filed At. _____

Object Ident. _____

Ident. By _____

Signature

PLANE COORDINATE POSITION DATA

State _____ Zone _____

X _____

Y _____

Estab. By _____

Agency

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the intersection of U.S. Forest Road 419N and 537N, go East along 537N 3.3 miles, then West about 1.8 Miles, then North 0.2 miles, then along fence for 29 chns. to corner.

Signature *David H. Kle...*

Title

CORNER DIVISION (11-11-77) OPLS 933

Headquarters

Date

7-77

7100-52 (3/68)

5

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set 2½" x 30" iron pipe with brass cap.
 Pipe is 23" in ground.
 Mound of stone to cap.

T. 6S., R. 30E.

S.4 S.3

1977

PLS 933

Stamped as shown:

ACCESSORIES: DESCRIBE NEW BY'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

A 9" fir bears N. 15°17' W. 45.6 ft.
 A 12" fir bears S. 68°25' E. 28.0 ft.

Set steel fence post 3' West of brass cap w/sign.
 Painted red band around bearing trees w/sign.

Work Done By T. Hamby Title Party Chief Date 6/23/77 State Registration No. _____
 or Agency _____

Certified Cor. Record Prepared? Yes No _____ Filed At: _____ Date _____

REMARKS

Index File No.

T.

R.

M.

Tract or Surv. No.

Cor.

12

13