


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1881 by Henry Meldrum, under Contract No. 380.

Surveyor General Record States:

40.00 set a pine post for 1/4 Sec. cor. from which:

A fir 16 in. in dia. brs N. 65° W., 11 lks distant.
A fir 11 in. in dia. brs S. 70° E., 25 lks distant.



No record of subsequent remonumentation found in County Records.

Description of corner evidence found:

I did not find the original corner post. I establish this corner at record bearing and distance from the remains of the original BT stump in Sec. 1.

From the corner point, the ORIGINAL BEARING TREE:

The remains of a 12" fir stump partially rotted bears N. 65° W. 7.3 ft. with axe marks and healing scar visible in bark and thin layer of wood.

A dead and down 5" fir bears S. 85° E. 13.0 ft. mkd. 1/4 S BT. This tree has slid down hill and I could not tell where it originally stood.

Description of monument and accessories I established to perpetuate the original location of this corner:

At the corner point: Set a 2 1/2"x30" galvanized iron pipe 27" in the ground with brass cap marked as shown: From which I scribe NEW BEARING TREES:

A 6" fir bears N. 41° E. 28.1 ft. mkd T6S R31E 1/4 S6 BT.
A 10" fir bears S. 8° W. 19.5 ft. mkd T6S R30E 1/4 S1 BT.


I nailed a brass washer marked "OPLS 598" to the BT blaze of both trees. Set a steel fence post 5 ft. West of corner. Corner is 55 feet South of dry creek bed and ravine. Used compass with 20° East variation and steel tape measuring to center of new BTs.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Robert D. Bagett

OREGON
JULY 12, 1963
ROBERT D. BAGETT
598

Sept. 30, 1976



Office of.....County..Surveyor..... County of..... Umatilla
State of..... Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

G-25
S-60-M