


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Frank W. Campbell under Contract No. 380 dated March 19, 1881:

Set Pine Post from which

Pine, 18" Dia., BRS. N80°E., 20 Lks. Dist.
Pine, 10" Dia., BRS. S86°W., 26 Lks. Dist.



Description of corner evidence found:

Found no original evidence.

Description of monument and accessories established to perpetuate the original location of this corner

Set 32" X 2" flanged iron pipe with brass cap marked:

T6S R30E

From which

1/4
S6 | S5
1979
PLS 346

Douglas Fir, 7" Dia., BRS. S84 1/4°E., 33.9 Ft. Dist.
Marked: 1/4 S5 BT

Douglas Fir, 19" Dia., BRS. N30°W., 37.7 Ft. Dist.
Marked: 1/2 S6 BT


6' iron fence post with "Survey Monument" sign within 5' of corner.

All B.T. have BT tag and painted red stripe. New BTs have brass washer stamped: PLS 346; nailed to lower blaze.

Office of County Surveyor County of Umatilla
State of Oregon, I hereby certify that the within instrument was filed in this office
for record on the day of
..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date 10-17-79
Rec'd By mjj
No. Q-1171-B



C-5