

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


E-3

History of original corner establishment:

Frank W. Campbell under Contract No. 380 dated March 19, 1881:

Set Pine Post From Which

- Pine, 20" Dia., BRS S24°W., 5 Lks Dist.
- Pine, 30" Dia., BRS N74°E., 12 Lks Dist.



Description of corner evidence found:

Found no original evidence.

Found unrecorded BTs (BRGS. and DISTs. are from corner point established at proportionate distance).

- Fir (dead), 32" Dia., BRS. S13°E., 38.3 Ft. Dist. with scribing visible on open blaze.
- Fir (dead), 24" Dia., BRS. S 5°W., 26.8 Ft. Dist. with scribing visible on open blaze.

Description of monument and accessories established to perpetuate the original location of this corner

Set 32" X 2" flanged iron pipe with brass cap marked:
From which

T6S R30E
1/4 S6
1/4 S7
1979
PLS 346

Ponderosa Pine, 10" Dia., BRS. N21 1/2°E., 26.5 Ft. Dist.
Marked: 1/4 S6 BT

Douglas Fir, 10" Dia., BRS. S45 1/4°E., 19.7 Ft. Dist.
Marked: 1/4 S7 BT

6" Iron Fence Post with "Survey Monument" sign within 5' of Corner.

New BTs have BT tag, painted red stripe and brass washer stamped: PLS 346; nailed to lower blaze.

Office of County Surveyor County of Umatilla
 State of Oregon, I hereby certify that the within instrument was filed in this office
 for record on the day of

..... by
 (COUNTY OFFICIAL) (DEPUTY)

E-3

Form R6-7100-57 (9/71)

RECEIVED BY
 Umatilla County Surveyor
 Date 10-17-79
 Rec'd By msj
 No. Q-1171-B

