

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


E-1

History of original corner establishment:

Frank W. Campbell under Contract No. 38 dated March 19, 1881:

Set Pine Post from which

Pine, 12" Dia., BRS. N34⁰E., 17 Lks. Dist.
Pine, 8" Dia., BRS. S60⁰W., 20 Lks. Dist.



Description of corner evidence found:

Found split stone and square post approximately 2" X 2" from which down lodgepole pine, 8" Dia.; the root hole of which BRS. S2⁰E., 10.6 Ft. Dist. (RE.; U.S. Forest Service Corner Records, Umatilla National Forest)

Description of monument and accessories established to perpetuate the original location of this corner

Set 32" X 2" flanged iron pipe with brass cap marked: T6S R30E
From which

Douglas Fir, 13" Dia., BRS. N46¹/₂⁰E., 16.7 Ft. Dist.
Marked: $\frac{1}{4}$ S5 BT

Douglas Fir, 9" Dia., BRS. S45¹/₂⁰E., 13.6 Ft. Dist.
Marked: $\frac{1}{4}$ S8 BT

6' iron fence post with "Attention" sign within 5' of corner.

All B.T. have BT tag and painted red stripe. New BTs have brass washer stamped: PLS 346; nailed to lower blaze.

T6S R30E
 $\frac{1}{4}$
S5
S8
1979
PLS 346

Office of _____ County Surveyor _____ County of Umatilla
State of Oregon _____, I hereby certify that the within instrument was filed in this office
for record on the _____ day of _____
_____ by _____
(COUNTY OFFICIAL) (DEPUTY)

REGISTERED
PROFESSIONAL
LAND SURVEYOR

ORIGON
MAY 6, 1955
WAYNE O. HARRIS
346

E-7

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor
Date 10-17-79
Rec'd By WJS
No. Q-1171-B