


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:



A 13"x9"x6" BASALT STONE
48" PINE N84W 15 LKS.

Description of corner evidence found:

POSSIBLE MOUND OF STONES
50" PINE SNAG N84W 9.9' SCRIBING VISIBLE

Description of monument and accessories established to perpetuate the original location of this corner:

SET A 2"x30" IRON PIPE WITH A BRASS-CAP MARKED: T6S R30E
 $\frac{1}{4}$
S10 S11
1978
PLS 346

14" PINE S59E 33.5' MARKED: $\frac{1}{4}$ S11 BT
12" PINE S50W 42.7' MARKED: $\frac{1}{4}$ S10 BT

ALL BT'S HAVE A RED PAINTED STRIPE AND BEARING TREE SIGNS. THE NEW BT'S HAVE A BRASS WASHER STAMPED PLS 346 NAILED TO THE LOWER BLAZE. THERE IS A STEEL FENCE POST ON LINE NEAR THE CORNER.



Office of... COUNTY SURVEYOR County of... UMATILLA

State of... OREGON I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19..... **RECEIVED SEP 11 1978**

Wayne O. Harris by (DEPUTY)

(COUNTY OFFICIAL)

G-17

S-59-118