


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1881 by Meldrum & Campbell under General Land Office Contract No. 380.

Surveyor General Record States:

Set post for cor. to sect's. 7-12-13-18. From which:

- A 20" Tamarack bears N 66 W, 13 lks.
- A 15" Tamarack bears S 77 E, 64 lks.
- A 12" Pine bears S 28 W, 3 lks.
- A 8" Pine bears N 59 E, 32 lks.



No record of subsequent remonumentation was found in County Records.

Description of corner evidence found:

Found original scribed post in mound of stone, from which:

Original BTs

- A 24" Pine, good condition, bears S28W, 2.0 ft., scribes visable.
- A 18" Pine, good condition, bears N66W, 8.6 ft., scribes visable.

No evidence of other BTs.

Description of monument and accessories established to perpetuate the original location of this corner

At position of post, I set 2½"x30" iron pipe with brass cap marked as shown, 26" in ground, from which:

New BTs

- A 16" Pine bears N36E, 47.0 ft. marked T6S R30E S7 BT.
- A 18" Pine bears S 8E, 23.3 ft. marked T6S R30E S18 BT.

Nailed brass washer in BT blaze.


Set steel fence post 5+ ft. North of corner.

Used steel tape and magnetic compass with 20° E declination.

Measured to face of blaze on original BTs and center of new BTs.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

OREGON
JULY 10, 1934
DUANE I. GRIFFITH
644



Office of Surveyor County of Umatilla
 State of Oregon I hereby certify that the within instrument was filed in this office
 for record on the 13 day of April, 1974, at o'clock m., (signed)
Ralph Thompson by
 (COUNTY OFFICIAL) (DEPUTY)

S-58-m
G-1