


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

NONE



Description of corner evidence found:

A MOUND OF STONES- NO RECORD

Description of monument and accessories I established to perpetuate the location of this corner:


I SINGLE PROPORTIONED THE DISTANCE BETWEEN THE SECTION CORNER TO THE WEST AND THE QUARTER CORNER TO THE EAST AND SET:

A 3"x30" IRON PIPE WITH A BRASS CAP MARKED W 1/16 S12
16 ST3
1978
PLS 346

FROM WHICH: 14" PINE S56W 19.7' MARKED W 1/16 S12 BT
16" PINE N02W 32.7' MARKED W 1/16 S12 BT

BOTH BT'S HAVE A BEARING TREE SIGN, AN ATTENTION SIGN, A RED PAINTED STRIPE AND A BRASS WASHER STAMPED PLS 346 NAILED TO THE LOWER BLAZE.

THIS SURVEY IS RECORDED ON USFS CONTRACT # 40-04R3-8-0999 AND UMATILLA COUNTY SURVEY # P-96



Office of COUNTY SURVEYOR County of UMATILLA
State of OREGON, I hereby certify that the within instrument was filed in this office
for record on the 17 day of OCTOBER, 1978
Wayne O. Harris by _____
(COUNTY OFFICIAL) (DEPUTY)

J-23