

USDA-FOREST SERVICE

Index  
File No. J-5

**CORNER RECORD (SEARCH)**

(Ref. FSM 7151.4)

Tract or  
Survey No. \_\_\_\_\_ No. Sec. Cor.


T 6S R. 30E

R.D. Ukiah County Umatilla

Merid. Willamette

N.F. Umatilla State Oregon

**CORNER DIAGRAM**



**DESCRIBE CORNER MONUMENT FOUND**

NONE

**DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND**

Ponderosa Pine, 22" Dia., BRS. S57°E., 49.5 Ft. Distance.  
with scribing visible on open blaze.

**PHOTO IDENTIFICATION DATA**

Photo No. \_\_\_\_\_

Filed At. \_\_\_\_\_

Object Ident. \_\_\_\_\_

Ident. By \_\_\_\_\_

*Signature*

**PLANE COORDINATE POSITION DATA**

State \_\_\_\_\_ Zone \_\_\_\_\_

X \_\_\_\_\_

Y \_\_\_\_\_

Estab. By \_\_\_\_\_

*Agency*

Signature

Title

Division

Headquarters

Date

7100-52-(3/68)

**DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER**

Corner is approximately 1000' East of North-South Road shown on  
Thompson Flat 7½ Minute Quad Map.

PLS

346

9/79

## CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set 32" X 2" Flanged iron pipe with brass cap marked:

T6S R30E

S7|S8

S18|S17

1979

PLS 346

9

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

Douglas Fir, 14" Dia., BRS. N36 3/4<sup>o</sup>E., 67.6 Ft. Distance.  
 Douglas Fir, 11" Dia., BRS. S42 <sup>o</sup>W., 21.7 Ft. Distance.  
 Douglas Fir, 9" Dia., BRS. N38 3/4<sup>o</sup>W., 17.9 Ft. Distance.  
 6' Iron Fence Post with "Attention" Sign within 5' of Corner.

10

Work Done By Wayne O. Harris Title PLS Date 9/79 State Registration No. 346  
or AgencyCertified Cor. Record Prepared? YES XXX Filed At: Umatilla Co. Surveyor Office Date

11

REMARKS.

12

Index File No. 7-5 T.6S R.30E WM. Tract or Surv. No.Cor. 7|8  
18|17 13