

Index
File No. P-05

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

Tract or Survey No. _____ Cor. No. _____


T 6 S R. 31 E

R.D. NFJD County Umatilla

Merid. W.M.

N.F. Umatilla State Or.

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

None

2

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

PHOTO IDENTIFICATION DATA

Photo No. _____
Filed At. _____
Object Ident. _____
Ident. By _____

Signature

7

PLANE COORDINATE POSITION DATA

State Or. Zone North
X 2616385.433 meters
Y 152834.716 meters
~~Based on~~ NAD83 (1991)

8

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From jct of Hwy 395 & Burma Rd. Travel westerly on Burma Rd approx. 2.8 miles to a rd. jct. TAKE Spur Rd. Westerly (Left) approx 0.3 miles to a rd. jct. Take road to right (westerly) approx 0.7 miles to a rd. jct. Go left (westerly) approx 0.4 miles to section line. Go South Following along the section line approx 1800 feet to the corner.

4

Signature
Pave S. Randall

Title
Land Surveyor

Division

Headquarters
S.O.

Date
9/94

FS-7100-52 (3/68)

5

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

Set by proportion a 2 1/2" by 30" aluminum pipe with a 3 1/4" aluminum cap, set 22" in the ground and raised a mound of stone 3 feet in diameter by 1 foot high

T65R31E
1/4
519 | 520
PLS 1636
1994 9

ACCESSORIES : DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

25" Ponderosa Pine N 32 1/2° W 97.9 feet mkd "1/4 519" BT on Double Blaze
 23" Juniper N 15 1/4° E 135.5 feet mkd "1/4 520" BT on Double Blaze
 18" Ponderosa Pine S 73 1/4° E 57.6 feet mkd "1/4 520" BT on Double Blaze
 RM, 5/8 x 24" Rebar, with 1 1/2" aluminum cap, S 84° 11' W 68.78 feet
 mkd "USDA-FS RM 519 68 78 FT LS 1636"

10

Work Done By P. Gaylord Title Land Surveyor Date 9/94 State Registration No. PLS 1636
 or Agency

Certified Cor. Record Prepared? Yes No Filed At: Umatilla Co. Date 0

11

REMARKS

Index File No. P.05 T. 6. S. R. 31 E. M. W. M. Tract or Surv. No.

Cor.

12

13