


2-11

History of original corner establishment:

Original survey by Meldrum and Campbell, Contract No. 380, 1881:

Set a basalt stone 24"x14"x3 in a mound of stone for 1/4 sec. corner.



Description of corner evidence found:

Found a basalt stone, 24"x14"x3" with faint illegible chisel marks, lying loose on top of a mound of stone, 4 ft. diameter and 6" high. We accept the center of the stone mound as the original corner point.

Description of monument and accessories established to perpetuate the original location of this corner:

At the corner point as previously described, we set a 2"x30" Galvanized Iron Pipe, 22" in the ground to bedrock with orig. corner stone buried alongside and supported in a mound of stone 5 ft. dia. at base to cap.

With brass cap attached, marked:

From which we mark new BT's:

A 12" Douglas Fir scribed "1/4 S33 BT" on a double blaze bears N43° W 45.0 ft.

And a 12" Ponderosa Pine, scribed "1/4 S4 BT" on a double blaze, bears S30°W 117.9 ft.

Brass washer marked "LS 1099" nailed to lower blaze of new BT's.

Corner location established and perpetuated in accordance with our contract, 1979 USFS Cadastral Survey Specifications and 1973 BLM Survey Manual.

Staff Compass and Steel Chain. Declination = 18 1/2° E.

August 19, 1982

Witnesses: Gary Langlitz, Greg Orton, Jeff Anderson

T6S
 R
 31
 E
 1/4 S33
 S4
 T7S
 PLS 1099
 1982



Office of... Surveyor County of... Umatilla
 State of... Oregon I hereby certify that the within instrument was filed in this office
 for record on the... 18... day of... January , 1983
David H. K. by
 (COUNTY OFFICIAL) (DEPUTY)

2-11

RECEIVED BY
 Umatilla County Surveyor
 Date _____
 Rec'd By _____
 No. 83-03-B