


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: Corner established in 1881 by Henry Meldrum under General Land Office Contract No. 380.

Surveyor General Records (notes) states:
Set a fir post for: 1/4 Sec. Cor.
Pine 10 in. in dia. bears N38°W, 45 lks.
Pine 24 in. in dia. bears S40°W, 42 lks.



(No subsequent remonumentations in county records)

Description of corner evidence found:

Found a 24 in. pine, live in good condition, with healed-over blazes, bearing N38°W, 29.7 ft. from the corner position.

Found a 36 in. pine, live, in good condition with scribing visible, bearing S45°W, 27.7 ft. from the corner position.

Description of monument and accessories established to perpetuate the original location of this corner


Set a 30 in. x 2½ in. iron pipe with brass cap marked as shown, 26 in. in the ground and placed a mound of stone around the pipe for the 1/4 corner between Secs. 31 & 6.

Set a steel fence post approximately 5 ft. West from corner with Attention sign attached.

Used steel tape and magnetic compass with declination = 20°E.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Douglas M. Ferguson
OREGON
JULY 12, 1968
DOUGLAS M. FERGUSON
848



Office of County Surveyor County of Grant State of Oregon
I hereby certify that the within instrument was filed in this office for record on the 18 day of Nov., 1972, at 1 o'clock Pm., (signed) Douglas M. Ferguson by [Signature] (DEPUTY)
(COUNTY OFFICIAL)

2-3