


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

A-13

History of original corner establishment:

ESTABLISHED IN 1884 BY FRANK W. CAMPBELL:

Set a basalt stone 22 inches by 13 inches by 8 inches, 16 inches in the ground for closing corner for Section 3 and 4 marked. "CC"



With 3 notches on east and west edges in a mound of stones 2 feet high by 4½ feet at the base.

Description of corner evidence found:

A basalt stone, 20" x 10" x 3", firmly set and projecting 3 inches above the ground. The stone is marked with 3 notches on the east and west edges, and "CC" on the south face.

Description of monument and accessories | established to perpetuate the original location of this corner:

Moving the corner stone aside, I set in its place a 2½" x 30" iron pipe, 20" into the ground in a mound of stones, with a 3" brass cap marked:

From which:

- A 10" pine bears S. 30°E., 21 links (13.9 Ft.) scribed T. 6S., R. 32E., S. 3 CC BT.
- A 10" pine bears S. 13°W., 21 links (13.9 ft.) scribed T. 6S., R. 32E., S. 4 CC BT.

T. 5S.	
S33	
S4	S3
C.	C.
T. 6S.	R. 32E.
LS 1636	
1982	

Deposit the marked stone alongside iron pipe.



I hereby certify the above corner was perpetuated as hereon described in July 1982. Witness: Scott McMullin

Office of COUNTY SURVEYOR County of UMATILLA  
 State of OREGON, I hereby certify that the within instrument was filed in this office  
 for record on the 11 day of August, 1982  
David H. Klein by \_\_\_\_\_  
 (COUNTY OFFICIAL) (DEPUTY)

A-13

RECEIVED BY  
 Umatilla County Surveyor—798-276  
 Date 8-82  
 rec'd by BoS  
 i.o. 82-120-R