


A-21

History of original corner establishment:

This corner was originally established by Frank Campbell in 1884. The original notes state that at the corner a 18"by15"by8" basalt stone was set 12" in the ground for closing corner for Sections 1 and 2, marked "CC", with one notch on the east and 5 notches on the west edges from which:

A 20" tamarack bears S31°E-27 lks (17.8 ft), marked T6S R32E S1 BT.

A 10" pine bears S78°W-141 lks (93.1 ft), marked T6S R32E S2 BT.



In 1982, the corner was recovered by LS 1636. The recorded corner certificate states that the corner was reestablished by measurements from original bearing trees, and a 2 1/2" by 30" iron pipe with brass cap was set 20" in the ground with a mound of stone from which: ...See Page 2 ...

Description of corner evidence found:

Found a 2 1/2" by 30" galv. iron pipe with flared flange and a 2 1/2" brass cap protruding 8" from a stone mound from which:

A 25" pon. pine bears S6°E-46.76' to a nail in the west side of tree, with scribing visible on a partly healed blaze. (1982 bearing tree).

A 19" pon. pine bears S79 1/2°W-93.1' with scribing visible on a partly healed blaze which has been previously opened. (Original bearing tree).

A 12" douglas fir bears S73°W-22.4' with healed blaze. (1982 bearing tree).

A 18" down western larch snag bears S31°E-17.8' to root hole and stump remains with visible scribing under tree. (Original bearing tree).

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

William R. Wells

**OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106**

Description of monument and accessories established to perpetuate the original location of this corner:

This corner is likely to be destroyed by a new timber sale road. I set a 20" by 5/8" iron rod to bedrock with a 1 1/2" aluminum cap marked as shown. Buried monument by LS 1636 horizontally next to the new monument. The top of the new monument is 6" below the rut in the road at the corner point. From the new monument:

A reference monument bears S13 1/2°E-145.18', marked RM NW S1 CC 145.18 FT LS 1106 1986. An arrow points toward the corner point.

A reference monument bears S78 1/2°W-132.26' marked RM NE S2 CC 132.26 FT LS 1106 1986. An arrow points toward the corner point.

The angle between the two reference monuments, as observed from the corner point is 92°13', measured with a theodolite. Reference monuments are 5/8"by 30" iron rods with 1 1/2" aluminum caps. A 6' steel fence post with sign 54-9 attached is set within one foot of each reference monument.

Painted face of blaze and a 6" red band around each bearing tree. Attached sign 54-3 and 54-9 to each bearing tree.

Monument cap is marked:

T5S
S35

Used steel tape and staff compass with 19°E declination, measured to the center of the bearing trees.

```

S2 | S1
  C | C
-----
T6S R32E
LS 1106
1986

```

This corner was remonumented on April 7, 1986.

Office of...County Surveyor..... County of...Umatilla.....

State of...Oregon..... I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

RECEIVED BY

Form R6-7100-57 (9/71)

Umatilla County Surveyor

★ U.S. GOVERNMENT PRINTING OFFICE - 1983-793-276

Date 4-25-86

Rec'd by SA

No. 86-34-R

A-21

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

A-21


History of original corner establishment:

An 18" pine bears S78°W-141 lks (93.1 ft) with scribe marks visible on a partly healed blaze.

A stump hole with an 18" larch lying alongside bears S 31° E-27 lks (17.8 ft) with scribes "CC" visible.

The following bearing trees are stated on the recorded certificate to have been marked in 1982:

A 10" pine bears S59°E-16½ lks (10.9 ft), scribed T6S R32E S1 CC BT.
A 9" fir bears S73°W-34 lks (22.4 ft), scribed T6S R32E S2 CC BT.



Description of corner evidence found:

Description of monument and accessories | established to perpetuate the original location of this corner:

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of...County...Surveyor..... County of...Umatilla.....
State of...Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

A-21

Form R6-7100-57 (9/71)
RECEIVED BY
Umatilla County Surveyor
Date 4-25-86
Rec'd By JA
No. 86-31-R