

History of original corner establishment:

Corner location determined by proportionate measurement during survey performed in 1968-1980 by the Bureau of Land Management,

Set an iron post, 28 ins. long, 2 1/2 ins. diam., 20 ins. in the ground, in a mound of stone, 2 1/2 ft. base to top, with brass cap marked:


from which:

A Pine, 14 ins. diam. bears N 34°E 251 1/2 lks. dist., mkd. X BT.

A Pine, 9 ins. dia. bears N 81°W 84 1/2 lks. dist., mkd. X BT.

No suitable trees available within limits to the S.

T5S R32E
S 31
S6 | S5
T6S R32E
CC
1968



Description of corner evidence found:

Found an iron pipe, 2 1/2 ins. diam., firmly set, with brass cap attached, marked: U.S. Dept. of Interior Bureau of Land Management

from which:

The 1968 BLM bearing trees,

An 18" Ponderosa Pine, alive with scribing visible on a partially healed blaze, bears N 34°E 171.0 ft. (Record 166.0 ft.)

And a 12" Ponderosa Pine, alive and well-healed, bears N 81°W 48.1 ft. (Record 55.8 ft.)

T5S R32E
S 31
S6 | S5
T6S R32E
CC
1968

Description of monument and accessories established to perpetuate the original location of this corner:

None

Magnetic Compass (20° East Declination)
Steel Tape

Sept. 8, 1984

Witnesses:

Gary Langlitz, LS 1099
Ray Crapo
Greg Orton



Office of Surveyor County of Umatilla
State of Oregon, I hereby certify that the within instrument was filed in this office for record on the 08th day of October, 1984
David Krumbein by Beth Cochran
(COUNTY OFFICIAL) (DEPUTY)

Ans