

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Frank W. Campbell under G.L.O. contract number 468, dated April 12, 1883, set a pine post 3' long and 3" square 24" in the ground from which:

- A Fir, 24" dia., S58°E, 19 lks.
- A Fir, 12" dia., N40°W, 12 lks.

U.S. Cadastral Surveyors under special instructions Group Numbers 350 and 643 found a mound of stone, 2 ft. base, 1 ft. high, from which the remains of the original BTs:


- A decayed fir stump, S58°E, 19 lks., with scribing visible.
- A fir, 20" dia., N40°W, 12 lks., with healed blaze.

(Continued on Page 2 of 2.)

Description of corner evidence found:

I found a 2 1/2" iron pipe with a brass cap marked: in a mound of stone, from which:

- A decayed stump, S58°E, 12.5 ft. with fragmentary scribing.
- A Douglas Fir, 21" dia., N40°W, 7.9 ft., with a healed blaze.
- A Ponderosa Pine, 21" dia., S30°E, 14.8 ft., with scribing visible.
- A White Fir, 11" dia., N80°W, 15.5 ft., with a healed blaze.
- A White Fir, 9" dia., N77°E, 14.2 ft., with a healed blaze.



Description of monument and accessories established to perpetuate the original location of this corner:

I painted the blaze of the BTs and a 6" band around them red and attached new BT tags and "Attention" signs. I drove a 6' steel fence post within 5' of the corner and attached an "Attention" sign.

Measured to center of BTs using steel tape and staff compass. Magnetic declination set at 20 1/4°E.

Oct. 30, 1986



Office of..... County of.....
 State of..... I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19....
 by
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
 Umatilla County Surveyor
 Date 12-11-86
 Rec'd By KA
 No. 86-132-M

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


History of original corner establishment:

(Continued from Page 1 of 2.)

At the corner point they set a 2 1/2" X 28" iron post with a brass cap marked; in a mound of stone from which new BTs:

- A pine, 19" dia., S30°E, 22 1/2 lks.
- A fir, 9" dia., N83 1/2°W, 23 1/2 lks.
- A fir, 7" dia., N77°E, 21 1/2 lks.

1/4
S25 | S30
R32E | R33E
T6S
1967



Description of corner evidence found:

Description of monument and accessories established to perpetuate the original location of this corner:

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Fayette S. Munro

OREGON
JULY 13, 1979
FAYETTE S. MUNRO
1832

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19....

..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
Umatilla County Surveyor

GPO-798-276

Date _____

Rec'd By _____

No. 86-132-M

Pg. 2