

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:
 Quarter cor. Sec. 29 & 32 of T.6S. R.32E., W.M.
 Corner originally set by Frank Campbell under
 Contract No. 468 dated 1883.

Index: V-7

Set post, 3' long, 3 ins. square, 24 ins. on ground,
 for 1/4 Sec. Cor. marked 1/4S on N. face, from which
 A fir, 24 ins. diam., brs. N.67°E., 59 lks. dist.,
 marked 1/4S BT. A tamarack, 10 ins. diam., brs.
 S.79°W., 11 lks. dist., marked 1/4S BT.
 A dependent resurvey was made by the BLM under special
 instructions dated 1967. They found the original larch
 bearing tree and set a standard BLM monument marked
 as shown at the corner point.

1	DIAGRAM	1
1	BLM brass cap	1
1		1
1	T6S R32E	1
1	S29	1
1	1/4----	1
1	S32	1
		1
	1968	1
		1

They set the following new bearing trees: A Fir, 7 ins. diam., bears
 N.24°E., 29 1/2 lks. dist. mkd. 1/4 S29 BT. A Fir, 9 ins. diam., bears
 S.58°E., 30 lks. dist., mkd. 1/4 S32 BT.

Description of corner evidence found:


Found the corner monument as described from which:
 A 20" dbh Western Larch bears S79 1/2°W, 7.3' with visible scribe.
 A 12" dbh Douglas Fir bears N24 1/2°E, 19.6' with healed blaze.
 A 14" dbh Douglas Fir bears S58 1/2°E, 19.9' with healed blaze.

Description of monument and accessories I established to perpetuate the
 original location of this corner:


Cleared brush and debris from corner and set new bearing trees as
 follows:

A 8" dbh Douglas Fir bears S42 1/2°W, 39.6' scribed 1/4 S32 BT.
 The bearings are true based on the GPS bearings to the surveyed steel
 post which bears S88°41'E, 49.4'.
 An aluminum washer stamped RLS 852 is nailed between the letters B and T.
 on the new tree. All the BT's have LSM and BT signs attached.
 Painted 6" red bands around all the trees and painted the
 scribe blazes red.

This work was done May 27, 1994.



David L. Haddock



Office of _____ County of _____
 State of _____, I hereby certify that the within instrument was filed
 in this office for record on the _____ day of _____, 19____.

(COUNTY OFFICIAL)

(DEPUTY)

RECEIVED BY

Umatilla County Surveyor

Date 7-94

Rec'd By KR

No. 94-95-R