

Index

File No. X-22

T6S

R32E

Merid. Willamette

R.D.

N.F.

CORNER RECORD (SEARCH)

Ref. FSM 7151.4

North Fork John Day

Umatilla

Tract or

Survey No

County Umatilla

State Oregon

Cor.

No.

x

Corner Diagram

1

W--

16

C---C

S36

1968

1 Describe corner monument found

1 Standard BLM brass cap stamped as shown in the corner diagram.

1

1

1

1

x

Photo Identification Data

Photo No.

filed at

Object Ident.

Ident. by

Signature

1 Describe bearing trees or other official accessories found

1 A 9" Ponderosa Pine bears S2 E, 7.9' with the top recently broken out.

1 A 13" Ponderosa Pine bears N17 1/2 W, 22.5' with partially visible scribing.

1

1

1

x

Plane Coordinate Position Data

State

Zone

X

Y

Estab. by

Agency

1 Describe corner location relative to near-by features, also how to reach corner

1 From the junction of roads 55 and 5507, follow road 5507 southeast 1.7

1 miles to road 175. Follow road 175 0.4 miles to a point 120' before the fence

1 crossing of the road. Follow the posted line east 500' to the corner.

1

1

x

Signature

Title

Division

Headquarters

Date

7100.52

David L. Hadduck
Land Surveyor

Pendleton, OR

July 1988

CORNER RECORD (PERPETUATION)

X ----- X
 Monument: Describe new monument set, or work done to preserve existing monument

Set steel guard post 5' west of the monument and attached Forest Service Land Survey Monument and Property Boundary signs.

X ----- X
 Accessories: Describe new BT's witness objects etc. established, or work done to preserve existing evidence

Established a new bearing tree. This tree is a 9" Ponderosa Pine which bears S20 1/2 E, 11.4' from the corner. Scribed this tree CW1/16 S36 BT and nailed an aluminum washer stamped RLS 852 between the letters B and T. Made bands around all three trees and painted the bands and the scribe blazes red. Attached Forest Service Land Survey Monument and Bearing Tree signs to each tree.

X ----- X

Work done by	David L. Haddock	Title	Land Surveyor	Date	July 1988	State Registration No.	
Certified cor. record prepared?	yes	x	no	Filed at	Pendleton, OR	or Agency	852
				Date	August 1988		

X ----- X

REMARKS

X-11 T16 P32E NM