


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

E-9

**History of original corner establishment:**

Original survey by Frank Campbell, under Contract No. 468, dated April 12, 1883.  
 Set a pine post, 4 ft. long, 4 ins. square, 24 inches in the ground for corner to sec's 4, 5, 8 and 9, marked T6S S4 on NE  
 R33E S9 on SE  
 S8 on SW  
 S5 on NW



Faces, with 5 notches on S and 4 notches on E edges  
 from which:

- A Pine, 24 ins. dia. bears N11°E 41 lks. Dist., marked T6S R33E S4 BT.
- A Pine, 6 ins. dia. bears S40°E 63 lks. Dist., marked T6S R33E S9 BT.
- A Pine, 24 ins. dia. bears S48°W 9 lks. Dist., marked T6S R33E S8 BT.
- A Pine, 24 ins. dia. bears N42°W 20 lks. Dist., marked T6S R33E S5 BT.

**Description of corner evidence found:**

Found the remains of three original bearing trees:  
 A 24" Ponderosa Pine snag, (orig. SW bearing tree), approx. 20' tall, with scribing "T6S R33E S8 BT" visible on an unhealed double blaze,  
 A 24" Ponderosa Pine snag, (orig. NW bearing tree), approx. 30 ft. tall, with scribing "S R33E S5 BT" visible on an unhealed double blaze,  
 And a 20" Ponderosa Pine, dead and down, with scribing "T6S R33E S4 BT" visible on an unhealed double blaze.  
 Also found a steel fence post with BLM location tag near corner location.  
 No evidence of the original SE bearing tree or the original corner post was found.

**Description of monument and accessories established to perpetuate the original location of this corner:**

The original corner point is determined at record distances from the blazed faces of the remaining original bearing trees.  
 At the corner point we set a 2"x30" galvanized iron pipe, 26" in the ground, with brass attached marker:  
 from which:

- |   |          |
|---|----------|
| The original BT's   | S5   S4  |
| A 24" Ponderosa Pine snag bears S58°W, 6 <sup>9</sup> ft.     | S8   S9  |
| A 24" Ponderosa Pine snag bears N38°W, 14 <sup>2</sup> ft.    | PLS 1099 |
| A 20" Ponderosa Pine windfall bears N13°E 27 <sup>3</sup> ft. | 1984     |

- And new bearing trees
- A 12" Western Larch, scribed "T6S R33E S4 BT" on a double blaze, bears N17°E 58.6 ft.
  - A 12" Engleman Spruce, scribed "T6S R33E S9 BT" on a double blaze bears S5°E, 56<sup>7</sup> ft.
  - A 14" Douglas Fir, scribed "T6S R33E S8 BT" on a double blaze bears S56°W, 38<sup>2</sup> ft.
  - And an 8" Douglas Fir, scribed "T6S R33E S5 BT" on a double blaze bears N15°W, 18.4 ft.

Attached a brass washer, marked "LS 1099" to face of lower blaze on all new BT's.  
 Reset found steel fence post approx. 5 ft. west of corner and attached U.S.F.S. "Attention" and "Property Boundary" signs to post.  
 Corner located approx. 5' N. of E-W fence.  
 Compass Declination: 20°E  
 Steel tape

August 1, 1984

Witnesses:  
 Gary Langlitz, LS 1099  
 Ray Crapo  
 Greg Orton



Office of Surveyors County of Umatilla  
 State of Oregon I hereby certify that the within instrument was filed in this office  
 for record on the day of October 1984  
David Krumber by Billy Cochran  
 (COUNTY OFFICIAL) (DEPUTY)

E-9

84-154-R