

CORNER RECORD (SEARCH)


(Ref. FSM 5161.4)

Tract or Survey No. **North Fork John Dav Unit** Cor. No. **AP-490**

T. 6 S. R. 33 E.
Merid. Willamette

R.D. North Fork John Day County Umatilla
N.F. Umatilla State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Found a 5/8" rebar, with the 2" core of a melted aluminum cap, projecting 3" out of the ground.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

6" Lodgepole Pine Snag, N. 17 1/2 E., 27.0 feet, with burnt out blaze.
4" by 2' high Lodgepole Pine stub, N. 82 W., 10.6 feet, with burnt out blaze.

PHOTO IDENTIFICATION DATA

Photo No.
Filed At.
Object Ident.
Ident. By

Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the junction of roads 52 and 5507 travel southerly on 5507 approximately 0.55 miles. Then walk westerly approximately 200 feet to the corner.

PLANE COORDINATE POSITION DATA

State: Zone:

X:

Y:

Datum:

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

10/21/1997

FS-7100-52 (3/97)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

RM, 5/8" X 24" rebar with yellow plastic cap stamped "UMATILLA N.F.", set 19" in the ground, N. 53 1/2 E., 16.1 feet.

RM, 5/8" X 24" rebar with red plastic cap stamped "UMATILLA N.F.", set 22" in the ground, S. 27 1/2 E., 20.7 feet.

Work Done By D. Schlaich Title Land Surveyor Date 10/21/1997 State Registration No. _____
or Agency _____
Certified Corner Record Prepared ? Yes No Filed At: _____ Date _____

REMARKS

USDA-FOREST SERVICE

Index
File No.

CORNER RECORD (SEARCH)
(Ref. FSM 7151.4)

Tract or
Survey No. NFJD Unit

Cor.
No. AP-490

T. 6 S. R. 33 E.
Merid. WILLAMETTE

R.D. NFJD
N.F. UMATILLA

County UMATILLA
State OREGON

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

PHOTO IDENTIFICATION DATA

Photo No.:
Filed At:
Object Ident.:
Ident. By:

Signature

DESCRIBE CORNER-RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the jct. of roads 52 and 5507 travel southerly on 5507 approx. 0.55 miles. Then walk westerly approx. 200 feet to the corner.

PLANE COORDINATE POSITION DATA

State: Oregon Zone: North
X: 2,470,002.71'
Y: 496,593.11'
Datum: NAD1927

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

07-1993

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

5/8" by 36" rebar, with a 3 1/4" aluminum cap, flush with the ground, marked "NFJD WILDERNESS AP-490 RLS 2308 1993".

ACCESSORIES : DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

6" Lodgepole Pine, N. 81 1/2° W., 10.6 ft., mkd. "WB/490"BT" on double blaze.

6" Lodgepole Pine, N. 18° E., 27.0 ft., mkd. "WB/490"BT" on double blaze.

Both BT's have a 3/4" brass washer stamped "RLS 2308" nailed next to "BT" scribing on lower blaze.

Work Done By **D. Schlaich**

Title Land Surveyor

Date **07-1993**

State Registration No.
or Agency

Certified Cor. Record Prepared ? **NO**

Filed At:

Date

REMARKS

Index File No.

T.

6 S.

R.

33 E.

M.

W.M.

Tract or Survey No.

NFJD Unit

Cor.

AP-490