

CERTIFIED RECORD OF LAND CORNER MONUMENTATION


S-25

History of original corner establishment:

U.S. Cadastral Surveyors under special instructions Group Numbers 350 and 643 set a 2 1/2" X 28" iron post with a brass cap marked:

Post was 16" in the ground, in a stone mound. From the corner:

N1/16
S25 | S30
1968



A Fir, 12" dia., S70°E, 25 lks.
A Fir, 7" dia., S31°W, 15 lks.

Description of corner evidence found:

I found a 2 1/2" iron pipe with a brass cap marked: in a stone mound. From the corner:

N1/16
S25 | S30
1968

A White Fir, 8" dia., S31°W, 9.9 ft. with a healed blaze.
A Douglas Fir, 13" dia., S70°E, 16.5 ft. with a healed blaze. This tree was dying.

Description of monument and accessories established to perpetuate the original location of this corner:

I marked a new BT:

A Tamarack, 12" dia., S66 3/4°E, 91.7 ft., marked: N 1/16 S30 BT

BTs have blaze and 6" band painted red, BT tags and "Land Survey Monument" signs. New BT has, additionally, an alum. "PLS 1832" washer nailed to the bottom of the blaze. There is a 6' steel fence post with a "Land Survey Monument" sign within 5' of the corner.

Measured to center of BTs using steel tape and staff compass. Magnetic declination set at 20 1/4°E.

Oct. 30, 1986



Office of..... County of.....
 State of..... I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

RECEIVED BY
 Umatilla County Surveyor
 Date 12-11-86
 Rec'd By KA
 No. 86-133-M

GPO-788-276