


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

7-1

History of original corner establishment:

Corner originally established by Frank W. Campbell under GLO contract number 468, dated April 12, 1883. Surveyor General record states:




Set a pine post 3 ft long 3 ins square 24 inches in the ground for $\frac{1}{4}$ sec cor marked $\frac{1}{4}$ S on W face from which:
 A fir 24 ins dia brs S58°E 19 lks dist marked $\frac{1}{4}$ S BT
 A fir 12 ins dia brs N40°W 12 lks dist marked $\frac{1}{4}$ S BT
 Corner remonumented in 1967 by James E. Jelley, et al, BLM Group no. 350. His notes state: The $\frac{1}{4}$ cor of secs 25 and 30, monumented with a mound of stone 2 ft base 1 ft high from which the remains of the original bearing trees; A decayed fir stump, size indeterminate, bears S58°E 19 lks dist with scribes visible. A fir 20 ins diam bears N40°W 12 lks dist with healed blaze. At the corner point set an iron post in a mound of stone 2 ft base to top with brass cap marked; (markings shown below) from which new bearing trees: A pine 19 ins diam bears S3°E 22 $\frac{1}{2}$ lks dist marked $\frac{1}{4}$ S30 BT (1967). A fir 9 ins diam bears N83 $\frac{1}{2}$ °W 23 $\frac{1}{2}$ lks dist marked $\frac{1}{4}$ S25 BT (1967). A fir 7 ins diam bears N77°E 21 $\frac{1}{2}$ lks dist marked $\frac{1}{4}$ S25 BT (1978).

No record of subsequent monumentation found in Umatilla County survey records.
Description of corner evidence found:

Found a standard BLM brass cap marked as shown, in a mound of stone.

Original BTs:

Found an approximate 40 inch diam fir stump S58°E 12.5 feet, rotted with scribes visible.
 Found a 21 inch diameter Fir N40°W, 7.9 feet, sick and dying with blaze evident.



BLM BTs:

Found a 9 inch diameter Fir N77°E, 14.2 feet, sick and dying with blaze evident.
 Found a 11 inch diameter Fir N83 $\frac{1}{2}$ °W, 15.5 feet, sick and dying with blaze evident.
 Found a 21 inch diameter Pine S3°E, 14.8 feet, live and vigorous with scribes visible.

Found a steel fencepost approximately 3 feet North with 54-4 and 54-2 signs attached.

Description of monument and accessories established to perpetuate the

original location of this corner: From the existing found BLM brass cap monument:

New BT:

A 27 inch diameter Ponderosa Pine bears S40°W, 72.67 feet marked $\frac{1}{4}$ S25 BT
 Painted a 6 inch red band around all BTs and attached 54-3 and 54-9 signs.

I hereby certify that the above corner point was perpetuated as hereon described on July 17, 1987.

Witnesses: Greg Blackman, Rick Robinson and Jeff Petersen.



I used a steel tape and magnetic compass in the establishment of new accessories. I used 17° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of Survey Dept County of Umatilla
 State of OR I hereby certify that the within instrument was filed in this office
 for record on the 17 day of August, 1987
David A. Lambson by James E. Jelley
 (COUNTY OFFICIAL) (DEPUTY)

87-472