

V-2


History of original corner establishment:

Corner originally established by Frank W. Campbell under GLO contract number 468, dated April 12, 1883. Surveyor General record states:

Set basalt stone 18x10x4 ins 12 ins in the ground for cor of secs 29, 30, 31 and 32 marked with 1 notch on S and 5 notches on E edges from which:

- A Pine 30 ins dia brs N29°E 35 lks dist marked T6S R33E S29 BT
- A Pine 30 ins dia brs S33°E 38 lks dist marked T6S R33E S32 BT
- A Pine 24 ins dia brs S44°W 105 lks dist marked T6S R33E S31 BT
- A Pine 40 ins dia brs N82°W 107 lks dist marked T6S R33E S30 BT

Corner remonumented in 1977 by Craig L. Wanless, BLM Group no. 350. His notes state: The cor of secs 29, 30, 31 & 32, determined at record bearing and distance from the remains of the original bearing trees: A decayed pine stump, size indeterminate, bears S33°E 38 lks dist with scribes visible. A pine snag 26 in diam bears S44°W 105 lks dist with scribes visible. A root hole bears N82°W 107 lks dist with a down pine alongside 44 in diam no marks visible. At the corner point set an iron post with brass cap marked; (markings shown below) from which new bearing trees: A grand fir 12 ins diam bears N33°E 23 lks dist marked T6S R33E S29 BT. A grand fir 8 ins diam bears S34°E 29½ lks dist marked T6S R33E S32 BT. A grand fir 13 ins diam bears S51°W 46 lks dist marked T6S R33E S31 BT. A grand fir 11 ins diam bears N65°W 21 lks dist marked T6S R33E S30 BT. No record of subsequent monumentation found in Umatilla County survey records.




Description of corner evidence found:

Found standard BLM brass cap monument marked as shown below:
BLM BTs:

- Found a 12 inch diameter Grand Fir N33°E, 23 lks dist live and vigorous with scribes visible.
- Found a 11 inch diameter Grand Fir S34°E, 29½ lks dist, sick & dying, scribes visible.
- Found a 13 inch diameter Grand Fir S51°W, 46 lks dist, live & sickly, scribes visible.
- Found a 11 inch diameter Grand Fir N65°W, 21 lks dist, live and sickly with scribes visible.

Original BTs:

- Found a Pine snag 18 ins diam S44°W, 105 lks dist with scribes visible.
- Found a Pine stump, S33°E, 38 lks dist rotted with BT scribe visible.



See map of survey dated August, 1987.

Description of monument and accessories established to perpetuate the

original location of this corner: Raised mound of stone around existing found BLM brass cap monument 3 ft. base to top of cap from which:

New BTs:

- A 11 inch diameter Ponderosa Pine bears S58°E, 83.91 feet marked T6S R33E S32 BT
- A 11 inch diameter Ponderosa Pine bears S72°W, 58.10 feet marked T6S R33E S31 BT
- A 14 inch diameter Ponderosa Pine bears N15°W, 48.94 feet marked T6S R33E S30 BT

Set a steel fencepost approximately 5 feet North with 54-4 sign attached.

I painted a 6 inch red band around all BTs and attached 54-3 and 54-4 signs.

I hereby certify that the above corner point was perpetuated as hereon described on July 14, 1987.



I used a steel tape and magnetic compass in the establishment of new accessories. I used 17° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of Survey Dept. County of Umatilla
 State of OR, I hereby certify that the within instrument was filed in this office
 for record on the 24 day of August, 1987
David D. Krumbein by Kathleen K. Ambrey
 (COUNTY OFFICIAL) (DEPUTY)

87478