


V-9

History of original corner establishment:

Corner originally established by Frank W. Campbell under GLO contract number 468, dated April 12, 1883. Surveyor General record states:

- Set a pine post 4 ft long 4 ins square 24 ins in ground for cor to secs 28, 29, 32 and 33 marked T6S S28 on NE, R33E S33 on SE, S32 on SW and S29 on NW faces with 1 notch on S and 4 notches on E edges from which:
- A Pine 30 ins dia brs N25°E 27 lks dist marked T6S R33E S28 BT
- A Pine 6 ins dia brs S22°E 4 lks dist marked T6S R33E S33 BT
- A Pine 8 ins dia brs S31°W 15 lks dist marked T6S R33E S32 BT
- A Pine 6 ins dia brs N18°W 8 lks dist marked T6S R33E S29 BT



No record of subsequent monumentation found in Umatilla County survey records. Description of corner evidence found:

NONE

See map of survey dated August, 1987.

Description of monument and accessories established to perpetuate the original location of this corner: At position determined by survey, I set a 2 1/2" x 30" aluminum pipe with aluminum cap marked as shown, 28 inches in the ground, from which;

- New BTs:
- A 1" x 66" steel fencepost, driven 50" in the ground bears N45°E, 10.15 feet
- A 6 inch diameter Western Larch bears S1°E, 13.21 feet marked X BT
- A 10 inch diameter Western Larch bears S46°W, 15.09 feet marked T6S R33E S32 BT
- A 7 inch diameter Western Larch bears N45°W, 47.55 feet marked S29 BT

I painted a 6 inch red band around all BTs and attached 54-3 and 54-9 signs.

Set a steel fencepost approximately 5 feet North with 54-9 and 54-2 signs attached.

I hereby certify that the above corner point was perpetuated as hereon described on July 29, 1987.

Witnesses: Greg Blackman, Rick Robinson and Jeff Petersen.



I used a steel tape and magnetic compass in the establishment of new accessories. I used 17° East magnetic declination and the distances are to a 50d spike driven in the right side of the root crown. I attached a brass washer marked OPLS 644 to the BT blaze.

Office of Survey Dept. County of Umatilla  
 State of OR, I hereby certify that the within instrument was filed in this office  
 for record on the 24 day of August, 1987  
David H. Kramlein by Richard Kramlein  
 (COUNTY OFFICIAL) (DEPUTY)

87-47-c