

Index
File No.

CORNER RECORD (SEARCH)


(Ref. FSM 5151.4)

Tract or
Survey No.

Tower Unit

Cor.
No. AP-205T. 6 S. R. 34 E.
Merid. WillametteR.D. North Fork John Day
N.F. UmatillaCounty Umatilla
State Oregon

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

Found a 5/8" rebar with 3 1/4" aluminum cap, projecting 2" out of the ground.

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

8" Lodgepole Pine Snag, N. 78 E., 12.0 feet, with scribing visible on double blaze.
8" Lodgepole Pine Snag, N. 47 W., 14.2 feet, with scribing visible on double blaze.

PHOTO IDENTIFICATION DATA

Photo No.
Filed At.
Object Ident.
Ident. By

Signature

DESCRIBE CORNER LOCATION RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the jct. Of roads 5226 and 5226-200 travel northwesterly on 5226 approx. 0.10 miles. The corner is located westerly approx. 100 feet from the road.

PLANE COORDINATE POSITION DATA

State: Zone:

X:

Y:

Datum:

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

10/27/1997

FS-7100-52 (3/97)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

ACCESSORIES: DESCRIBE NEW BT'S WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE.

9" Lodgepole Pine, S. 44 W., 45.5 feet, scribed "WB/205" "BT" on double blaze.
16" Subalpine Fir, S. 88 1/2 W., 62.3 feet scribed "WB/205" "BT" on double blaze.

Work Done By D. Schlaich Title Land Surveyor Date 10/27/1997 State Registration No. _____
or Agency _____
Certified Corner Record Prepared? Yes No Filed At: _____ Date _____

REMARKS

Index

File No.

T. 6 S. R. 34 E.

Merid. WILLAMETTE

CORNER RECORD (SEARCH)

(Ref. FSM 7151.4)

R.D. NFJD

N.F. UMATILLA

County UMATILLA

State OREGON


Tract or

Survey No. Tower Unit

Cor.

No. AP-205

CORNER DIAGRAM



DESCRIBE CORNER MONUMENT FOUND

NONE

DESCRIBE BEARING TREES OR OTHER OFFICIAL ACCESSORIES FOUND

NONE

PHOTO IDENTIFICATION DATA

Photo No.:

Filed At.:

Object Ident.:

Ident. By:

Signature

DESCRIBE CORNER RELATIVE TO NEAR-BY FEATURES, ALSO HOW TO REACH CORNER

From the jct. of FS rds. 5226 and 5226-200 travel northwesterly on 5226 approx. 0.10 miles. The corner is located westerly approx. 100 feet from the road.

PLANE COORDINATE POSITION

State: Oregon Zone: North

X: 2,499,093.53'

Y: 511,431.43'

Datum: NAD1927

Signature

D. Schlaich

Title

Land Surveyor

Division

Headquarters

S.O.

Date

09-1993

FS-7100-52 (3/68)

CORNER RECORD (PERPETUATION)

MONUMENT: DESCRIBE NEW MONUMENT SET, OR WORK DONE TO PRESERVE EXISTING MONUMENT

5/8" by 36" rebar, with a 3 1/4" aluminum cap, 35" in the ground, marked "NFJD WILDERNESS TOWER UNIT AP-205 RLS2308 1993".

ACCESSORIES: DESCRIBE NEW BT's WITNESS OBJECTS ETC. ESTABLISHED, OR WORK DONE TO PRESERVE EXISTING EVIDENCE

8" Lodgepole Pine, N. 47° W., 14.2 ft., mkd. "WB/205""BT" on double blaze.

8" Lodgepole Pine, N. 78° E., 12.0 ft., mkd. "WB/205""BT" on double blaze.

Work Done By D. Schlaich

Title Land Surveyor

Date 09-1993

State Registration No.
or Agency

Certified Cor. Record Prepared ? NO

Filed At:

Date

REMARKS

Index File No.

T.

6 S.

R.

34 E.

M.

W.M.

Tract or Survey No.

Cor.

AP-205